

# BOARD OF SCHOOL EDUCATION HARYANA BHIWANI

Quotation No. 107/SDE

Quotation Notice

Date: 08.11.2024

Online quotations are invited from the registered Contractor for the mentioned Work below and Quotations must be uploaded to the Secretary Board of School Education Haryana, Bhiwani by E-mail address: [ratesbseh@gmail.com](mailto:ratesbseh@gmail.com) by 02:00 PM 18-11-2024 the latest.

Name of work : **Repair, Plastering, distempering and exterior painting, door/window replacement, granite work etc. in Kothi No. AA-2.**

Sr. No./HSR NO.	Discription of item	Qty.	Unit
1/5.45	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. Asper HSR 5.45	57.68	Sqm
2/11.6.2	15 mm cement plaster on the rough side of single or half brick wall of mix : 11.6.2 : 1:6 (1 cement: 6 fine sand)	57.68	Sqm
3/30.16.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. as per HSR 30.16.1	10.00	Sqm
4/30.22	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. As per HSR 30.22	394.60	Sqm
5/11.58	Providing and applying two coats white cement based putty of approved brand and manufacturer, over plastered surface and grinding the surface smooth with sand paper to get an even and smooth finish including cost and carriage of all material , labour charges, scaffolding, sundries etc. complete as per HSR 11.58	97.14	Sqm
6/11.64.1	"Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : 11.64.1 : New work (two or more coats) over and including water thinnable priming coat with cement primer"	394.60	Sqm
7/11.95.1	"Finishing walls with Acrylic Smooth exterior paint of required shade : 11.95.1 : New work (Two or more coat applied @ 1.67 litre/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) as per HSR 11.95.1"	57.68	sqm
8/30.37.2	"Finishing walls with Acrylic Smooth exterior paint of required shade : 30.37.2 ; Old work (One or more coat applied @ 0.90 litre/10 sqm)."	227.75	Sqm
9/30.28.1	"Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work as per HSR 30.28.1"	286.60	Sqm
10/10.50.1	"Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent."	7.32	Sqm

# BOARD OF SCHOOL EDUCATION HARYANA BHIWANI

11/8.27.2	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Granite wor	9.14	Mtr.
12/10.58	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer ) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete. as per HSR 10.58	38.87	Sqm
13/5.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.HSR 5.7.4 In cement mortar	0.59	Cum
14/5.43.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. HSR 5.43.1	33.29	Sqm
15/5.29.1	HSR Item 5.29.1 -Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and belo	2.00	Nos.
16/12.37.1	HSR Item 12.37.1 -Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 1. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	1.41	Sqm
17/12.157.1	HSR Item 12.157.1.2 -Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) : 1.2. For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	85.00	Kgs.
18/12.159.2	HSR Item 12.159.2 -Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): 2. With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm	4.50	Sqm

# BOARD OF SCHOOL EDUCATION HARYANA BHIWANI

19/30.10.1	HSR Item 30.10.1 -Replacing sand stone slabs in roofing, laid in cement mortar 1:4 (1 cement : 4 coarse sand), including necessary repairs and cement pointing with same mortar complete, including disposal of rubbish to dumping ground, all complete as per direction of Engineer-in-Charge. 1. Red sand stone slabs 30 to 50 mm thick	1.86	Sqm
20/5.7	HSR Item 5.70 -Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	5.00	Cum
21/13.21.1	HSR Item 13.21.1 -Supply and fixing Windows frames (Chowkhats) including mullions consisting frame fabricated from sheet roll formed out of 1.2mm thick galvanized sheet as per IS:277 (Base steel as per IS 513) with zinc of 120 gm/sqm and Powder coated with pure Polyester powder up to 50 microns (as per approved colour), 3 Nos. 100mm butt - hinges 2mm thick, 6 Nos. 1.2mm thick CRCA electroplated stiffner, 6 Nos. M.S hold fast with split and tail welded to stiffner plate 200mm long, receiver for aldrop, weld less corner assembly with brackets and screws, M.S tie rod 50mm x 25mm to be fixed at bottom finished with powder coated total thickness of coating 0.6mm of approved shade, fixed in position including the cost of cement concrete for 1:2:4 for fixing lugs complete in all respects as per drawing, design, specification and entire satisfaction of Engineer-in-charge.	7.00	Mtr.
22/13.21.2	HSR Item 13.21.2 -Supply and fixing Windows frames (Chowkhats) including mullions consisting frame fabricated from sheet roll formed out of 1.2mm thick galvanized sheet as per IS:277 (Base steel as per IS 513) with zinc of 120 gm/sqm and Powder coated with pure Polyester powder up to 50 microns (as per approved colour), 3 Nos. 100mm butt - hinges 2mm thick, 6 Nos. 1.2mm thick CRCA electroplated stiffner, 6 Nos. M.S hold fast with split and tail welded to stiffner plate 200mm long, receiver for aldrop, weld less corner assembly with brackets and screws, M.S tie rod 50mm x 25mm to be fixed at bottom finished with powder coated total thickness of coating 0.6mm of approved shade, fixed in position including the cost of cement concrete for 1:2:4 for fixing lugs complete in all respects as per drawing, design, specification and entire satisfaction of Engineer-in-charge. 2. Door Frame of size 125mm x 60mm with 37mm wide double rebate for 35mm door shutter	9.00	Mtr.
23/7.28.2	"Half brick masonry with common burnt clay non-modular bricks of class designations 7.5 in superstructure above plinth level upto floor IV level 7.28.2 cement mortar 1:4 "	2.97	Sqm
24/12.53.2	"providing and fixing fly proof galvanized M.S. wire gauge to windows ..... 12.53.2 with 12mm mild steel U beading"	7.50	Sqm

### Terms & Conditions :-

1	The works shall be carried over as per PWD specifications, HSR-2021 & as desired by Engineer-in- Charge.
2	Conditionally, telegraphic quotations will not be accepted and liable to be rejected straightway.
3	All charges such as Royalty, Municipal Octroi and other all type of taxes as per Govt. Rule shall be paid by the contractor.
4	The quantity of works can be increase/decrease as per our requirements.
5	Nothing will be paid for damage done due to rain and any other act of God.

## BOARD OF SCHOOL EDUCATION HARYANA BHIWANI

6	The successful contractor must deposit 10% security amount of contract value after receiving the work order. Security amount will be released on request after successful completion of work.
7	Contractor has to be submitted his bill in duplicate after satisfactory completion of the work.
8	No material will be provided by the Board's office.
9	If, any other items of HSR except above mentioned will be paid same rates above or below of HSR as mentioned in work order.
10	The rates of non-schedule items shall be inclusive of fixing and installation complete in all respect and removal of old articles. All items should be ISI Mark and there shall not be extra charges for these items.
11	The unacceptable items shall be subject to replacement at the risk and the responsibility of the contractor.
12	The committee also reserves the right to relax any of the above mentioned conditions and reject all quotation altogether without assigning any reason.
13	In case of any dispute arises, the decision of the Secretary of the Board only shall be final.
14	The work shall have to be completed within 45 days after receiving the work order.
15	The completion period of work will be 45 days, which will be reckoned from the receiving the work order. The penalty @ 1% per day and maximum penalty 5% of the contract value will be levied for late completion of work.
16	Rate should be quoted along with G.S.T. on self letter head or in given Annexure x.



Assistant Secretary(SDE Cell)  
for Secretary

# BOARD OF SCHOOL EDUCATION HARYANA BHIWANI

Quotation Notice No. 107/SDE

Quotation

Annexure: x  
Date:- 08-11-2024

Name of Work:- **Repair, Plastering, distempering and exterior painting, door/window replacement, granite work etc. in Kothi No. AA-2.**

Sr. No./ HSR No.	Description of item	Qty.	Unit	Quoted rate with GST per unit
1/5.45	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. As per HSR 5.45	57.68	Sqm	
2/11.6.2	15 mm cement plaster on the rough side of single or half brick wall of mix : 11.6.2 : 1:6 (1 cement: 6 fine sand)	57.68	Sqm	
3/30.16.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. as per HSR 30.16.1	10.00	Sqm	
4/30.22	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. As per HSR 30.22	394.60	Sqm	
5/11.58	Providing and applying two coats white cement based putty of approved brand and manufacturer, over plastered surface and grinding the surface smooth with sand paper to get an even and smooth finish including cost and carriage of all material , labour charges, scaffolding, sundries etc. complete as per HSR 11.58	97.14	Sqm	
6/11.64.1	"Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : 11.64.1 : New work (two or more coats) over and including water thinnable priming coat with cement primer"	394.60	Sqm	
7/11.95.1	"Finishing walls with Acrylic Smooth exterior paint of required shade : 11.95.1 : New work (Two or more coat applied @ 1.67 litre/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) as per HSR 11.95.1"	57.68	sqm	
8/30.37.2	"Finishing walls with Acrylic Smooth exterior paint of required shade : 30.37.2 ; Old work (One or more coat applied @ 0.90 litre/10 sqm)."	227.75	Sqm	
9/30.28.1	"Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work as per HSR 30.28.1"	286.60	Sqm	

## BOARD OF SCHOOL EDUCATION HARYANA BHIWANI

10/10.50.1	<p>Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.</p> <p>Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.</p>	7.32	Sqm	
11/8.27.2	<p>Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.</p> <p>Granite wor</p>	9.14	Mtr.	
12/10.58	<p>Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer ) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete. as per HSR 10.58</p>	38.87	Sqm	
13/5.7.4	<p>Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.HSR 5.7.4</p> <p>In cement mortar</p>	0.59	Cum	
14/5.43.1	<p>Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. HSR 5.43.1</p>	33.29	Sqm	
15/5.29.1	<p>HSR Item 5.29.1 -Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :</p> <p>Of area 3 sq. metres and belo</p>	2.00	Nos.	
16/12.37.1	<p>HSR Item 12.37.1 -Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:</p> <p>1. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws</p>	1.41	Sqm	
17/12.157.1	<p>HSR Item 12.157.1.2 -Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) :</p> <p>1.2. For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)</p>	85.00	Kgs.	



## BOARD OF SCHOOL EDUCATION HARYANA BHIWANI

18/12.159.2	HSR Item 12.159.2 -Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): 2. With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm	4.50	Sqm	
19/30.10.1	HSR Item 30.10.1 -Replacing sand stone slabs in roofing, laid in cement mortar 1:4 (1 cement : 4 coarse sand), including necessary repairs and cement pointing with same mortar complete, including disposal of rubbish to dumping ground, all complete as per direction of Engineer-in-Charge. 1. Red sand stone slabs 30 to 50 mm thick	1.86	Sqm	
20/5.7	HSR Item 5.70 -Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	5.00	Cum	
21/13.21.1	HSR Item 13.21.1 -Supply and fixing Windows frames (Chowkhats) including mullions consisting frame fabricated from sheet roll formed out of 1.2mm thick galvanized sheet as per IS:277 (Base steel as per IS 513) with zinc of 120 gm/sqm and Powder coated with pure Polyester powder up to 50 microns (as per approved colour), 3 Nos. 100mm butt - hinges 2mm thick, 6 Nos. 1.2mm thick CRCA electroplated stiffner, 6 Nos. M.S hold fast with split and tail welded to stiffner plate 200mm long, receiver for aldrop, weld less corner assembly with brackets and screws, M.S tie rod 50mm x 25mm to be fixed at bottom finished with powder coated total thickness of coating 0.6mm of approved shade, fixed in position including the cost of cement concrete for 1:2:4 for fixing lugs complete in all respects as per drawing, design, specification and entire satisfaction of Engineer-in-charge.	7.00	Mtr.	
22/13.21.2	HSR Item 13.21.2 -Supply and fixing Windows frames (Chowkhats) including mullions consisting frame fabricated from sheet roll formed out of 1.2mm thick galvanized sheet as per IS:277 (Base steel as per IS 513) with zinc of 120 gm/sqm and Powder coated with pure Polyester powder up to 50 microns (as per approved colour), 3 Nos. 100mm butt - hinges 2mm thick, 6 Nos. 1.2mm thick CRCA electroplated stiffner, 6 Nos. M.S hold fast with split and tail welded to stiffner plate 200mm long, receiver for aldrop, weld less corner assembly with brackets and screws, M.S tie rod 50mm x 25mm to be fixed at bottom finished with powder coated total thickness of coating 0.6mm of approved shade, fixed in position including the cost of cement concrete for 1:2:4 for fixing lugs complete in all respects as per drawing, design, specification and entire satisfaction of Engineer-in-charge. 2. Door Frame of size 125mm x 60mm with 37mm wide double rebate for 35mm door shutter.	9.00	Mtr.	
23/7.28.2	Half brick masonry with common burnt clay non-modular bricks of class designations 7.5 in superstructure above plinth level upto floor IV level 7.28.2 cement mortar 1:4	2.97	Sqm	

# BOARD OF SCHOOL EDUCATION HARYANA BHIWANI

24/12.53.2	providing and fixing fly proof galvanized M.S. wire gauge to windows.. 12.53.2 with 12mm mild steel U beading"	7.50	Sqm	
------------	-------------------------------------------------------------------------------------------------------------------	------	-----	--

(Space to be used by the Quotationer for quotation the rates of the items in figure. The same is to be send back to Board by E-mail on [ratesbseh@gmail.com](mailto:ratesbseh@gmail.com) after filling up the rates).

It is certified that rates of the above items quoted by me are correct and I am ready to do this wotk on given Terms & Conditions.

1. Name of Quotationer \_\_\_\_\_
2. Name of Firm/Agency/Contractor \_\_\_\_\_
3. Address Firm/Agency/Contractor \_\_\_\_\_
4. PAN No. \_\_\_\_\_
5. GST No. (Mandatory) \_\_\_\_\_
6. Mobile No./E-mail Id \_\_\_\_\_
7. Regn. No. of the firm/agency/Contractor \_\_\_\_\_
8. Beneficiary Name \_\_\_\_\_
9. Account No. of the Quotationer \_\_\_\_\_
10. I.F.S.C. Code of the Bank Branch \_\_\_\_\_
11. Name of the Bank in which Quotationer has account \_\_\_\_\_
12. Name of the Branch of the Bank \_\_\_\_\_

Signature of Quotationer  
With seal/stamp