



Quotation No.37..... /S.D.E.

Date: 24.09.2026

Online quotations are invited from the registered Contractor for the below mentioned Work for which Quotations must be uploaded to the Secretary Board of School Education Haryana, Bhiwani by E-mail address: ratesbseh@gmail.com by 02:00 PM 30.09.2026 the latest.

Name of work:- Abstract for providing and placing Filter media in Slow sand filter at education board Bhiwani.

Sr No	Description Of Items	Qty	Unit	Rates with GST
1	Dismantling of C.I. sluice valve including stacking of useful materials within a lead of 50 metres above 150mm sluice valve as per HSR 5.64.2	2.00	Nos.	
2	Top Layer : Fine sand screened, cleaned and washed and graded (effective size 0.2 to 0.4 mm with uniformity coefficient 2.0 to 3.0) from Ghaggar or other approved source	36.59	Cum.	
3	Second layer Coursed sand screened, cleaned and washed and graded from 3 mm to 6 mm (from Ghaggar or approved equivalent quarry)	7.96	Cum.	
4	Third layer Bajri (coursed) screened and washed graded from 20 mm to 25 mm (from Ghaggar or approved equivalent quarry)	12.09	Cum.	
5	Fourth Layer Bajri (coursed) screened and washed graded from 20 mm to 25 mm (from Ghaggar or approved equivalent quarry)	7.96	Cum.	
6	Bottom Layer Broken stone, screened, washed and graded from 50 mm to 75 mm (from Ghaggar or approved equivalent quarry)	7.96	Cum.	
7	C.I. Sluice valve : Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) : 22.162.3.1 150mm dia class I	2.00	Nos.	

Terms & Conditions :-

1	The works shall be carried over as per PWD specifications as desired by Engineer- in-Charge.
2	Conditionally, telegraphic quotations will not be accepted and liable to be rejected straightway.
3	All charges such as Royalty, Municipal Octroi and other all type of taxes as per Govt. Rule shall be paid by the contractor.
4	The quantity of works can be increase/decrease as per our requirements.



5	Nothing will be paid for damage done due to rain and any other act of God.
6	The contractor must deposit 10% security amount of total contract value before completion of work. Security amount will be released on request after successful completion of work.
7	Contractor has to be submitted his bill in duplicate after satisfactory completion of the work.
8	No material will be provided by the Board's office.
9	If, any other items of HSR except above mentioned will be paid same rates above or below of HSR as mentioned in work order.
10	The rates of non-schedule items shall be inclusive of fixing and installation complete in all respect and removal of old articles. All items should be ISI Mark and there shall not be extra charges for these items.
11	The unacceptable items shall be subject to replacement at the risk and the responsibility of the contractor.
12	The committee also reserves the right to relax any of the above mentioned conditions and reject all quotation altogether without assigning any reason.
13	In case of any dispute arises, the decision of the Secretary of the Board only shall be final.
14	Rate should be quoted along with G.S.T. on self letter head or in given Annexure x.



Assistant Secretary (M.M.)
HBSE, Bhiwani



Annexure: X


Quotation Notice No.....37...../S.D.E.

Date: -...24.09.2026

Name of work:- Abstract for providing and placing Filter media in Slow sand filter at education board Bhiwani.

Sr No	Description Of Items	Qty	Unit	Rates with GST
1	Dismantling of C.I. sluice valve including stacking of useful materials within a lead of 50 metres above 150mm sluice valve as per HSR 5.64.2	2.00	Nos.	
2	Top Layer : Fine sand screened, cleaned and washed and graded (effective size 0.2 to 0.4 mm with uniformity coefficient 2.0 to 3.0) from Ghaggar or other approved source	36.59	Cum.	
3	Second layer Coursed sand screened, cleaned and washed and graded from 3 mm to 6 mm (from Ghaggar or approved equivalent quarry)	7.96	Cum.	
4	Third layer Bajri (coursed) screened and washed graded from 20 mm to 25 mm (from Ghaggar or approved equivalent quarry)	12.09	Cum.	
5	Fourth Layer Bajri (coursed) screened and washed graded from 20 mm to 25 mm (from Ghaggar or approved equivalent quarry)	7.96	Cum.	
6	Bottom Layer Broken stone, screened, washed and graded from 50 mm to 75 mm (from Ghaggar or approved equivalent quarry)	7.96	Cum.	
7	C.I. Sluice valve : Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) : 22.162.3.1 150mm dia class I	2.00	Nos.	

(Space to be used by the Quotationer for quotation the rates of the items in figure. The same is to be given back to Board by E-mail after filling up the rates) It is certified that rates of the above items is quoted by me are correct.





1. Name of Quotationer
2. Name of Firm/Agency/Contractor.....
3. Address Firm/Agency/Contractor.....
4. PAN No.
5. GST No. (Mandatory)
6. Mobile No./E-mail Id
7. Regn. No. of the firm/agency/Contractor
8. Beneficiary Name.....
9. Account No. of the Quotationer
10. I.F.S.C. Code of the Bank Branch.....
11. Name of the Bank in which Quotationer has account
12. Name of the Branch of the Bank

Signature of Quotationer
With seal/stamp

