



Quotation No. 99/J.E./MM

Quotation Notice

Date: 27-06-2024

Online quotations are invited from the registered Contractor for the mentioned Work below. Quotations must be uploaded to the Secretary Board of School Education Haryana, Bhiwani by E-mail address: ratesbseh@gmail.com by 02:00 PM 08-07-2024 the latest.

Name of work :- Construction of pump Chamber and storage tank for washing station in BSEH Campus Bhiwani.

Sr.no	Description	Qty	Unit
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth and lift up to 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge. 4.12.1 : All Kinds of soil	7.21	Cum.
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level: 6.1.7 : 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size)	0.98	Cum.
3	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	11.34	Sqm.
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding, wastage, overlaps, welded joints, spacer bars, chair, stays, hangers and annealed steel wire etc. complete in all respect below plinth level. 6.33.6 : Thermo-Mechanically Treated bars of grade Fe-500D or more.	128.74	Kg.
5	Brick work with common burnt clay non-modular bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	1.43	Cum.
6	Brick work with common burnt clay non-modular bricks of class designation 7.5 in superstructure above plinth level up to floor IV level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	2.32	Cum.
7	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. 6.25.2All works above plinth level up to floor IV level	1.45	Cum.
8	Half brick masonry with non modular fly ash bricks of class designation 10, conforming IS :12894, in super structure above plinth and up to floor IV level. Cement mortar 1 : 4 (1 cement : 4 coarse sand)	19.94	Sqm.
9	12 mm cement plaster of mix : 11.5.3 ; 1:4 (1 cement: 4 fine sand)	36.35	Sqm
10	15 mm cement plaster on the rough side of single or half brick wall of mix : 11.6.1 : 1:4 (1 cement: 4 fine sand)	34.70	Sqm.
11	Providing and applying two coats white cement based putty of approved brand and manufacturer, over plastered surface and grinding the surface smooth with sand paper to get an even and smooth finish including cost and carriage of all material , labour charges, scaffolding, sundries etc. complete	62.06	Sqm.
12	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : 11.64.1 : New work (two or more coats) over and including water thinnable priming coat with cement primer	31.16	Sqm.



हरियाणा विद्यालय शिक्षा बोर्ड, भिवानी

Board of School Education Haryana, Bhiwani

(Established Under Haryana Board of School Education Act, 1969)
(ISO 9001 : 2015 - Certified Organization)



भारत 2023 INDIA

13	Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	10.88	Sqm.
14	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 litre/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	29.69	Sqm.
15	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	2.52	Sqm.
16	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 250x16	1.00	Each
17	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 75mm	2.00	Each
18	10 cm thick (average) mud phaska of damped brick earth on roofs laid to slope consolidated and plastered with 25 mm thick mud mortar mixed with bhusa @ 35 kg per cum of earth and gobri leaping with mix 1:1 (1 clay : 1 cow dung) and covered with flat tile bricks, grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement and finished neat: With common burnt clay non-modular brick tile of class designation 10 as per HSR 9.11.1	9.09	sqm
19	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : in 75mmx75mm deep chase as per HSR 9.17.1	12.12	metre
20	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete. as per HSR 9.18	1.00	each
21	Providing and fixing pressed steel door frames conforming to IS: 4351, manufactured from commercial mild steel sheet of 2.0 mm thickness, including hinges, jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 2.00 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge: Fixing with adjustable lugs with split end tail to each jamb	4.20	mtr
22	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	5.18	Sqm

Terms & Conditions :-

1	The works shall be carried over as per PWD specifications, HSR-2021 & as desired by Engineer- in-Charge.
2	Conditionally, telegraphic quotations will not be accepted and liable to be rejected straightway.
3	All charges such as Royalty, Municipal Octroi and other all type of taxes as per Govt. Rule shall be paid by the contractor.
4	The quantity of works can be increase/decrease as per our requirements.
5	Nothing will be paid for damage done due to rain and any other act of God.
6	The successful contractor must deposit 10% security amount of contract value. Security amount will be released on request after successful completion of work.
7	Contractor has to be submitted his bill in duplicate after satisfactory completion of the work.



हरियाणा विद्यालय शिक्षा बोर्ड, भिवानी Board of School Education Haryana, Bhiwani

(Established Under Haryana Board of School Education Act, 1969)
(ISO 9001 : 2015 - Certified Organization)



8	No material will be provided by the Board's office.
9	If, any other items of HSR except above mentioned will be paid same rates above or below of HSR as mentioned in work order.
10	The rates of non-schedule items shall be inclusive of fixing and installation complete in all respect and removal of old articles. All items should be ISI Mark and there shall not be extra charges for these items.
11	The unacceptable items shall be subject to replacement at the risk and the responsibility of the contractor.
12	The committee also reserves the right to relax any of the above mentioned conditions and reject all quotation altogether without assigning any reason.
13	In case of any dispute arises, the decision of the Secretary of the Board only shall be final.
14	The work shall have to be completed within 45 days after receiving the work order.
15	The completion period of work will be 45 days, which will be reckoned from the receiving the work order. The penalty @ 1% per day and maximum penalty 5% of the contract value will be levied for late completion of work.
16	Rate should be quoted along with G.S.T. on self letter head or in given Annexure x.

Assistant Secretary (MM)
for secretary



हरियाणा विद्यालय शिक्षा बोर्ड, भिवानी Board of School Education Haryana, Bhiwani

(Established Under Haryana Board of School Education Act, 1969)
(ISO 9001 : 2015 - Certified Organization)



Annexure: x

Date:- 27-06-2024

Quotation Notice No . 99 /JE/MM

Quotation

Name of the Work:- **Construction of pump Chamber and storage tank for washing station in BSEH Campus Bhiwani.**

Sr.no	Description	Qty	Unit	Quoted Rates per unit with GST
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth and lift up to 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge. 4.12.1 : All Kinds of soil	7.21	Cum.	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level: 6.1.7 : 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size)	0.98	Cum.	
3	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	11.34	Sqm.	
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding, wastage, overlaps, welded joints, spacer bars, chair, stays, hangers and annealed steel wire etc. complete in all respect below plinth level. 6.33.6 : Thermo-Mechanically Treated bars of grade Fe-500D or more.	128.74	Kg.	
5	Brick work with common burnt clay non-modular bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	1.43	Cum.	
6	Brick work with common burnt clay non-modular bricks of class designation 7.5 in superstructure above plinth level up to floor IV level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	2.32	Cum.	
7	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. 6.25.2All works above plinth level up to floor IV level	1.45	Cum.	
8	Half brick masonry with non modular fly ash bricks of class designation 10, conforming IS :12894, in super structure above plinth and up to floor IV level. Cement mortar 1 : 4 (1 cement : 4 coarse sand)	19.94	Sqm.	
9	12 mm cement plaster of mix : 11.5.3 ; 1:4 (1 cement: 4 fine sand)	36.35	Sqm	
10	15 mm cement plaster on the rough side of single or half brick wall of mix : 11.6.1 : 1:4 (1 cement: 4 fine sand)	34.70	Sqm.	
11	Providing and applying two coats white cement based putty of approved brand and manufacturer, over plastered surface and grinding the surface smooth with sand paper to get an even and smooth finish including cost and carriage of all material , labour charges, scaffolding, sundries etc. complete	62.06	Sqm.	
12	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : 11.64.1 : New work (two or more coats) over and including water thinnable priming coat with cement primer	31.16	Sqm.	



हरियाणा विद्यालय शिक्षा बोर्ड, भिवानी Board of School Education Haryana, Bhiwani

(Established Under Haryana Board of School Education Act, 1969)
(ISO 9001 : 2015 - Certified Organization)



भारत 2023 INDIA

13	Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	10.88	Sqm.	
14	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 litre/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	29.69	Sqm.	
15	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	2.52	Sqm.	
16	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 250x16	1.00	Each	
17	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 75mm	2.00	Each	
18	10 cm thick (average) mud phaska of damped brick earth on roofs laid to slope consolidated and plastered with 25 mm thick mud mortar mixed with bhusa @ 35 kg per cum of earth and gobi leaping with mix 1:1 (1 clay : 1 cow dung) and covered with flat tile bricks, grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement and finished neat: With common burnt clay non-modular brick tile of class designation 10 as per HSR 9.11.1	9.09	sqm	
19	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : in 75mmx75mm deep chase as per HSR 9.17.1	12.12	metre	
20	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete. as per HSR 9.18	1.00	each	
21	Providing and fixing pressed steel door frames conforming to IS: 4351, manufactured from commercial mild steel sheet of 2.0 mm thickness, including hinges, jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 2.00 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge: Fixing with adjustable lugs with split end tail to each jamb	4.20	mtr	
22	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	5.18	Sqm	

(Space to be used by the Quotationer for quotation the rates of the items in figure. The same is to be send back to Board's E-mail address: ratesbseh@gmail.com after filling up the rates.

1. Name of Quotationer
2. Name of Firm/Agency/Contractor.....
3. Address Firm/Agency/Contractor.....
4. PAN No.



हरियाणा विद्यालय शिक्षा बोर्ड, भिवानी
Board of School Education Haryana, Bhiwani

(Established Under Haryana Board of School Education Act, 1969)
(ISO 9001 : 2015 - Certified Organization)



5. GST No. (Mandatory)
6. Mobile No./E-mail Id
7. Regn. No. of the firm/agency/Contractor
8. Beneficiary Name
9. Account No. of the Quotationer
10. I.F.S.C. Code of the Bank Branch.....
11. Name of the Bank in which Quotationer has account
12. Name of the Branch of the Bank

It is certified that rates of the above items quoted by me are correct and I am ready to do this work on given Terms & Conditions at page no. – 2 & 3.

Signature of Quotationer
With seal/stamp