



हरियाणा विद्यालय शिक्षा बोर्ड, भिवानी Board of School Education Haryana, Bhiwani

(Established Under Haryana Board of School Education Act, 1969)
(ISO 9001 : 2015 - Certified Organization)



भारत 2023 INDIA

Quotation No. 98/J.E./MM

Quotation Notice

Date: 27-06-2024

Online quotations are invited from the registered Contractor for the mentioned Work below and Quotations must be uploaded to the Secretary Board of School Education Haryana, Bhiwani by E-mail address: ratesbseh@gmail.com by **02:00 PM 08-07-2024** the latest.

Name of work : Construction of footpath in Herbal park and painting on Kerb stone & MS grills along 4 -lane road.

Sr. No.	Discription of item	Qty.	Unit
1/4.14.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	13.58	Cum
2/6.1.7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level: 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size)	9.06	Cum
3/34.2.2	Cast in Situ Cement Concrete M 20 Kerb with Channel Construction of cement concrete kerb with channel with top and bottom width 115 and 165 mm respectively, 250 mm high in M 20 grade PCC on M10 grade foundation 150 mm thick, kerb channel 300 mm wide, 50 mm thick in PCCM20 grade, sloped towards the kerb, kerb stone with channel laid with kerb laying machine, foundation concrete laid manually, all complete as per clause 408	97.54	Rmtr
4/10.30.1	Providing and laying of chequered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Medium shade pigment using 50% white cement and 50% Grey cement	59.46	Sqm
5/11.67.1	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	29.73	Sqm
6/11.78	Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	29.73	Sqm
7/30.22	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	479.28	sqm
8/11.67.1	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	479.28	Sqm
9/11.78	Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	479.28	Sqm
10/30.28.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	434.77	Sqm



Terms & Conditions :-

1	The works shall be carried over as per PWD specifications, HSR-2021 & as desired by Engineer-in- Charge.
2	Conditionally, telegraphic quotations will not be accepted and liable to be rejected straightway.
3	All charges such as Royalty, Municipal Octroi and other all type of taxes as per Govt. Rule shall be paid by the contractor.
4	The quantity of works can be increase/decrease as per our requirements.
5	Nothing will be paid for damage done due to rain and any other act of God.
6	The successful contractor must deposit 10% security amount of contract value after receiving the work order. Security amount will be released on request after successful completion of work.
7	Contractor has to be submitted his bill in duplicate after satisfactory completion of the work.
8	No material will be provided by the Board's office.
9	If, any other items of HSR except above mentioned will be paid same rates above or below of HSR as mentioned in work order.
10	The rates of non-schedule items shall be inclusive of fixing and installation complete in all respect and removal of old articles. All items should be ISI Mark and there shall not be extra charges for these items.
11	The unacceptable items shall be subject to replacement at the risk and the responsibility of the contractor.
12	The committee also reserves the right to relax any of the above mentioned conditions and reject all quotation altogether without assigning any reason.
13	In case of any dispute arises, the decision of the Secretary of the Board only shall be final.
14	The work shall have to be completed within 45 days after receiving the work order.
15	The completion period of work will be 45 days, which will be reckoned from the receiving the work order. The penalty @ 1% per day and maximum penalty 5% of the contract value will be levied for late completion of work.
16	Rate should be quoted along with G.S.T. on self letter head or in given Annexure x.

Assistant Secretary (MM)
for Secretary



हरियाणा विद्यालय शिक्षा बोर्ड, भिवानी Board of School Education Haryana, Bhiwani

(Established Under Haryana Board of School Education Act, 1969)
(ISO 9001 : 2015 - Certified Organization)



Annexure: x
Date:- 27-06-2024

Quotation Notice No. 98 /JE /MM

Quotation

Subject:- Construction of footpath in Herbal park and painting on Kerb stone & MS grills along 4 -lane road.

Sr. No./ HSR	Discription of item	Qty.	Unit	Quoted rate with GST per unit
1/4.14.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	13.58	Cum	
2/6.1.7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level: 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size)	9.06	Cum	
3/34.2.2	Cast in Situ Cement Concrete M 20 Kerb with Channel Construction of cement concrete kerb with channel with top and bottom width 115 and 165 mm respectively, 250 mm high in M 20 grade PCC on M10 grade foundation 150 mm thick, kerb channel 300 mm wide, 50 mm thick in PCCM20 grade, sloped towards the kerb, kerb stone with channel laid with kerb laying machine, foundation concrete laid manually, all complete as per clause 408	97.54	Rmtr	
4/10.30.1	Providing and laying of chequered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Medium shade pigment using 50% white cement and 50% Grey cement	59.46	Sqm	
5/11.67.1	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	29.73	Sqm	
6/11.78	Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	29.73	Sqm	
7/30.22	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	479.28	sqm	
8/11.67.1	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	479.28	Sqm	
9/11.78	Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	479.28	Sqm	
10/30.28.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	434.77	Sqm	



हरियाणा विद्यालय शिक्षा बोर्ड, भिवानी Board of School Education Haryana, Bhiwani

(Established Under Haryana Board of School Education Act, 1969)
(ISO 9001 : 2015 - Certified Organization)



(Space on pre page to be used by the Quotationer for quotation the rates of the items in figure. The same is to be send back to Board's E-mail address: ratesbseh@gmail.com after filling up the rates..

1. Name of Quotationer _____
2. Name of Firm/Agency/Contractor _____
3. Address Firm/Agency/Contractor _____
4. PAN No. _____
5. GST No. (Mandatory) _____
6. Mobile No./E-mail Id _____
7. Regn. No. of the firm/agency/Contractor _____
8. Beneficiary Name _____
9. Account No. of the Quotationer _____
10. I.F.S.C. Code of the Bank Branch _____
11. Name of the Bank in which Quotationer has account _____
12. Name of the Branch of the Bank _____

It is certified that rates of the above items quoted by me are correct and I am ready to do this work on given Terms & Conditions at page no. - 2.

Signature of Quotationer
With seal/stamp